Evidence of Performance

Air permeability of installationfoam

Test Report

No. 12-001850-PR01

(PB-K05-02-en-01)

Client Cantex Rubber

Milrooijseweg 47a 5258 KG. Berlicum The Netherlands

Installation foam (in-situ foam)

Cantex LDP-1000 Designation

Dimension Joint cross section 20 x 60 mm²

One-component, moisture curing PU-based installation foam Material

> The air permeability of the installation foam was determined in an "ideal" joint and in new condition on the basis of DIN 18542, Clause 7.2. The results cannot be used to demonstrate air tightness of linear connecting joints (gunned with foam) in practical

end-use applications. Special feautres

Result Air permeability in new condition

 $a < 0.1 \text{ m}^3 / [h \cdot m \cdot (daPa)^{2/3}]$

no measurable air flow

ift Rosenheim

04.07.2014

Wolfgang Jehl, Dipl.-Ing. (FH) **Deputy Head of Testing Department Building Material & Semifinished Products** Thomas Stefan, Dipl.-Ing. (FH) **Operating Testing Officer** Construction Product Testing



Basis

Test based on DIN 18542: 1999-01 *), Sealing of outside wall joints with impregnated sealing tapes made of cellular plastics, Clause 7.2, Air permeability *)

Test standard:

EN 12114: 2000-03

Test report 12-001850-PR01 (PB-K05-02-de-01) dated 19.10.2012

*) See explanations in test report

Representation of test

specimen



Instructions for use

This test report serves to demonstrate the above material property.

Validity

The data and results given relate solely to the tested and described specimen.

The effects of weathering and ageing have not been covered.

Notes on publication

The ift Guidance Sheet "Conditions and Guidance for the Use of ift Test Reports" applies.

The cover sheet can be used as an abstract.

Contents

The report comprises a total of 6 pages.

- 1 Object
- Procedure
- Results



Air permeability of installation foam
Test Report 12-001850-PR01 (PB-K05-02-en-01) dated 04.07.2014
Cantex Rubber, 5258 KG Berlicum (The Netherlands)



1 Object

1.1 Description of test specimen

The description is based on inspection of the test specimen at the **ift** Rosenheim. Item designations/ numbers as well as material specifications were given by the client.

Product designation Cantex LDP-1000

Material / Base One-component, moisture curing PU-based installation foam

(in-situ foam), colour light yellow

Density $14.5 - 16.5 \text{ kg/m}^3$

Cell structure Fine to medium sized pores

For more technical details refer to the Technical Data Sheet of the client.

For testing the installation foam was gunned into a test apparatus composed of square aluminium tubes, the specimens used for testing the air permeability of linear joints in accordance with DIN 18542, Clause8.2 and photo 5. Spacer disks inserted between the square tubes ensured uniform joint width of 20 mm. Joint depth was 60 mm.

3 joints of each 1,000 mm joint length were prepared for the test. After the time specified by the manufacturer to achieve full loading capacity, the installation foam protruding from the joint was cut off on both sides flush with the joint.

1.2 Representation of test specimen

The photographs were taken at the ift during testing.



Photo 1 Joints gunned with foam in test apparatus for linear joints in accordance with DIN 18542, mounted on window test rig

Air permeability of installation foam
Test Report 12-001850-PR01 (PB-K05-02-en-01) dated 04.07.2014
Cantex Rubber, 5258 KG Berlicum (The Netherlands)



2 Procedure

2.1 Sampling

The test specimens were selected by the client.

Delivered on 21 July 2014, by the client

Number 3 cans, including discharger and cleaner.

Registration No. 33005/001

Preparation The installation foam was gunned by the client of the testing

body into the test apparatus on 21 July 2014. During gunning the installation foam, the joint faces and the foam surfaces were wetted with water sprayed from a spray bottle. Prior to the test, the test apparatus including the foamed joints was also stored at standard atmosphere (23 °C, 50 % rel. hum idity).

2.2 Method/s

Basis

DIN 18 542 : 2009-07 Sealing of outside wall joints with impregnated sealing tapes

made of cellular plastics - Impregnated sealing tapes - Re-

quirements and testing (subtest as per Clause 8.2)

Since there is no comparable standard known for the objective of testing this installation foam, the test set arrangement was

based on this standard.

EN 12114 : 2000-03 *) Thermal performances of buildings - Air permeability of building

components and building elements - Laboratory test method

Boundary conditions as per standard specifications

2.3 Test equipment

Window test rig Device No.: 22200

2.4 Testing

Date/Period 29 July 2014

Test engineer Thomas Stefan, Dipl.-Ing. (FH)

Air permeability of installation foam
Test Report 12-001850-PR01 (PB-K05-02-en-01) dated 04.07.2014
Cantex Rubber, 5258 KG Berlicum (The Netherlands)



2.5 Test sequence

2.5.1 Test of air permeability

Illustration 1 below shows the test sequence (pressure steps) according to EN 12114 to determine the air permeability




Illustration 1 Test sequence (pressure steps)

The measurement results are used to determine linear air permeability [m³/(hm)] up to a test pressure difference of 1,000 Pa. Leakages of the test arrangement were determined by comparative measurement (zero measurement) during which the joints to be tested were masked air-tight. These leakages were then taken into account for the subsequent air permeability test of the joints. Thus only the air flow through the joints to be tested is determined.

3 Results

3.1 Test of air permeability in new condition

The test record lists the values and diagram 1 and 2 shows the plotted values. Diagram 2 shows also, for orientation, the requirements for evaluation of air permeability of linear joints as per DIN 4108, Part 2, expressed by the air permeability a where a δ 0.1 m 3 / [h m (daPa) $^{2/3}$].

The measurement results were obtained of joints in new condition with uniform joint widths and smooth, parallel joint faces, i.e. from an "ideal" joint. The effects and changes resulting from weathering and/or ageing, the different nature of the joint faces and any joint movements, have not been taken into account. Thus the results cannot be applied to any linear connecting joints (gunned with foam) in end use applications.

Air permeability of installation foam
Test Report 12-001850-PR01 (PB-K05-02-en-01) dated

04.07.2014 Cantex Rubber, 5258 KG Berlicum (The Netherlands)



3.2 Test record

Test record air permeability composite joints

Project No. 12-001850-PR01 File No. 12-001850

Basis of test EN 12114:2000-03

Thermal performance of buildings - Air permeability of building components and building elements -

Laboratory test method

Used test equipment Pst/022200 - LWW-Prüfstand Fensterprüfstand 1

Test sequence in accordante to DIN18542, 3 joints in cross section im Querschnitt 20 x 60 mm²

 Test specimen No.
 33005-001

 Date of test
 29.08.2012

 Testing personnal in charge
 Thomas Stefan

 Test engineer
 Thomas Stefan

Information to test configuration / Test method

Test method There are no deviations to the test method according standard/basis.

Ambient conditions Temperature 22,1 ℃ Air humidity 63,6 % Air pressure 968,7 hPa

The ambient conditions are in accordance with the standard requirements.

Testing

Partial water vapour pressure	p _w	1691,363961	Pa
Air tightness laboratory cond. Laborbed.	ρ	1,135409021	kg/m³
Air tightness reference cond.	ρ_{o}	1,1988	kg/m³

Test according to DIN EN 12114

| Width | x | Height | 977 | x | 1200 | in mm | Length | 3 | x | 1000 | in mm |

PRESSURE

3 pressure pulses with 1100 Pa X

Flow rate (volume) 1	Zero measurement (joints covered)								
Pa	50	73	106	154	224	325	473	688	1000
V in m³/h	*)	*)	*)	*)	*)	*)	*)	*)	*)
*) not measurable, V < 0,06 m³/h									

Joint length 3,00 m

Flow rate (volume) 2 - 1	Air permeability joint								
Pa	50	73	106	154	224	325	473	688	1000
V in m³/h	*)	*)	*)	*)	*)	*)	*)	*)	*)
V ₀ in m³/h	*)	*)	*)	*)	*)	*)	*)	*)	*)
joint length-related in m³/hm	*)	*)	*)	*)	*)	*)	*)	*)	*)


^{*)} not measurable, V < 0,06 m³/h


^{*)} not measurable, V < 0,06 m³/h

Air permeability of installation foam Test Report 12-001850-PR01 (PB-K05-02-en-01) dated

04.07.2014 Cantex Rubber, 5258 KG Berlicum (The Netherlands)







Graphic 1 Flow rate (volume V₀

Graphic 2 Joint length-related air permeability Q

Results air permeability composite joints	Results					
Parameters	Value	95%-confidence range	Unit			
Air flow rate coefficient C 1)2)		no measurable air flow	m³/(h Pa ⁿ)			
Leckageexponent n 2)		no measurable air flow				
1) Air flow rate through test specimen at a pressure differential of 1 I	Pa					
$^{(2)}$ C and n after the emperical air permeability equation $V = C \times \Delta p^n$						

The composite joint is in terms of DIN 4108-2, Clause 7, requirements a $< 0.1 \text{ m}^3/\text{[h m (daPa)}^{2/3}\text{]}$, air tight

Note:

The test was carried out in an ideal joint. Therefore the material characteristics of the foam was tested . Thus the results cannot be applied to any linear joints in end use applications.

ift Rosenheim 29.08.2012